

## PEMBANGUNAN SISTEM NOMBOR GILIRAN UNTUK KEGUNAAN MAJLIS BANDARAYA ISKANDAR PUTERI

RINGKASAN SENARAI KUANTITI

BIL.	BAHAGIAN	MUKA SURAT	JUMLAH (RM)
1	SITE : KAUNTER SETEMPAT & KAUNTER KHIDMAT PELANGGAN MBIP (MEDINI) MODEL : MYQ PREMIUM + MULTIMEDIA VSQ3010 SERIES	2/2	
JUMLAH KESELURUHAN			

• Semua kod pengaturcaraan dan penyelenggaraan sistem adalah hak milik MBIP

BIL.	KETERANGAN	UNIT	KUANTITI	KADAR (RM)	AMAUN (RM)
A	SITE : KAUNTER SETEMPAT & KAUNTER KHIDMAT PELANGGAN MBIP (MEDINI) MODEL : MYQ PREMIUM + MULTIMEDIA VSQ3010 SERIES  To supply & install queue management system device as below :-				
A.1	TOUCH SCREEN 17" MYQ KIOSK C/W THERMAL TICKET PRINTER MYQ KIOSK SOFTWARE CONSIST OF (BUILD IN KIOSK):  <ul style="list-style-type: none"> <li>• PROCESSOR INTEL(R) PENTIUM (R) GOLD G6400 4GB RAM 1TB HDD OR OTHERS SPEC INSTEAD</li> <li>• QUEUE MANAGER SERVER SOFTWARE WITH LICENSE</li> <li>• MULTIMEDIA SOFTWARE WITH LICENSE</li> <li>• CUSTOMER FEEDBACK WITH LICENSE</li> <li>• VOICE MODULE SOFTWARE WITH LICENSE</li> <li>• WINDOW 10 PRO WITH LICENSE</li> </ul>	-	1		
A.1.1	MULTIMEDIA CONTROLLER SHOW QUEUE NUMBER FOR EXISTING LED TV	-	3		
A.1.1.1	TOUCH SCREEN 9" COUNTER CUSTOMER FEEDBACK TERMINAL	-	13		
A.1.1.2	VIRTUAL COUNTER KEY PAD WITH LICENSE	-	14		
A.1.1.3	VOICE MODULE AMPLIFIER WITH 2PCS CEILING SPEAKER	-	1		
A.1.1.4	UPS 800VA 3WAYS BACK-UP BATTERY WITH VOLTAGE STABILIZATION	-	1		
A.1.1.5	ON-SITE INSTALLATION, SETUP, TESTING, COMMISSIONING & TRAINING	-	1		
A.1.1.6	POWER NETWORK SWITCH 24 PORT 10/100MBPS	-	1		
A.1.1.7	TO FORMAT & REPROGRAM EXISTING 5 UNITS TOUCH SCREEN 9" COUNTER CUSTOMER FEEDBACK TERMINAL & EXISTING 1 UNIT TOUCH SCREEN 9" TICKET PRINTER	-	1		
A.1.1.8	TO SUPPLY & INSTALL CAT6 CABLING WORK IN HIGH IMPACT PVC CONDUIT RUN ABOVE CEILING/ PARTITION/ COUNTER FROM POWER SUPPLY & OTHERS ACCESSORY	-	2		
A.1.1.9	TO SUPPLY & INSTALL TWIN CABLING WORK IN HIGH IMPACT PVC CONDUIT RUN ABOVE CEILING/ PARTITION/ COUNTER FROM VOICE MODULE WITH OTHERS ACCESSORY	-	2		
A.1.1.10	MAIN POWER SUPPLY CENTRALISED CONTROL BOX WITH AUTO TIMER & ACCESSORY	-	1		
A.1.1.11	TO SUPPLY & INSTALL 13AMP POWER SUPPLY OUTLET USING 2X2.5MM2 PVC + E CABLE IN HIGH IMPACT PVC CONDUIT RUN ABOVE CEILING/ PARTITION/ COUNTER FROM MAIN POWER SUPPLY CONTROL BOX & OTHERS ACCESSORY	-	17		
<b>JUMLAH KESELURUHAN (BIL A)</b>					